



Performing Arts
Division -
Technical Support
Unit

Tai Po Civic Centre

12 On Pong Road,
Tai Po, NT, HK

Phone
852-2665 4477
Fax
852-2667 4289

CONTACTS

Winnie POON

Senior Manager
(NTE) Venue
Direct Line
852-2694 2505

Yvonne CHAU

Manager (NTE)
Operations 2
ykwchau@lcsd.gov.hk

Direct Line
852-2694 2590
Fax Line
852-2693 4878

Dennes KWAN

Resident Technical
Manager (NTE)
dyykw@lcsd.gov.hk

Direct Line
852-2694 2571
Fax Line
852-2697 6747

GENERAL SET-UP

Tai Po Civic Centre Black Box Theatre operates on a 'bare-walls' touring policy. That is, all equipment is normally set-up and struck within the booking period. Hirers are reminded to allow sufficient preparation time to hang theatre masking, rig all overhead stage lighting and setup sound system.

INFORMATION

Full technical drawings available

Tai Po Civic Centre - Black Box Theatre

Basic Technical Information

V. 2021.10.21

Page 1 of 1

Hall size	12.30 x 10.00 x 5.80m (W x D x H) wall to wall	
Seats	<i>End Stage</i> <i>End Stage</i>	138 149
Stage size	<i>End Stage (138seating)</i> <i>End Stage (149seating)</i>	12.30 x 5.50m (W x D) 12.30 x 4.50m (W x D)
Stage Surface	Flat - black painted hardboard	
Flying system	4 Lighting Truss, 11 meters long with 12 socket outlets and 250kg max. loading for each truss 1 Lighting Box Truss, 11 meters long with 12 sockets outlets and 250kg max. loading.	
Stage Manager Desk	Locate at control booth	
Wardrobe	None	
Dressing Rooms	1 dressing room accommodates 6 persons	
Electrics	ETC ION lighting console, 1024 channels ETC Sensor 3 Dimmer x 60, 3kW each Additional power: 13A socket around the walls in the theatre	
Sound	DigiCo S21 mixing console QSC KLA12 Line Array Speaker QSC KLA181Subwoofer	
Projection	Panasonic PT-DZ870ELK, 8,500 ANSI Lumens	
Storage space	None	
Move-in	Entrance door size: 1.5 x 2.0m (W x H)	
Crossover	None	
Equipment	Black dance flooring: 2.00 x 12.50 (W x L), 3 rolls Iron, ironing board, and steamer	
Other Facilities	None	
Musical Instruments	Upright piano	
Comments	The above equipment is not-fix-installed, their availability has to be checked prior to booking period. All required equipment will be set-up during the booking sessions, please allow extra time for equipment set-up before performance or rehearsal.	